

# AASHTOWare

# Daily Work Report DWR Demo

Anita Muhly, P.E.  
Resident Engineer – Consultant Projects  
AWP DWR & Diaries Subcommittee Team Lead  
[Anita.MUHLY@odot.oregon.gov](mailto:Anita.MUHLY@odot.oregon.gov)  
Cell: 971-403-8522

January 18, 2023

Best way to Contact: Teams Chat!



# Agenda:

- 10 Min DWR Benefits**
- 25 Min GDPR to DWR Demo**
- 5 Min DWR Continued Resources**
- >10 Min Questions**



# DWR Benefits

- **No more Pay Notes!**
  - DWR holds all info for Payment to the Contractor
  - Daily information = more important, but end of the month pay notes do not exist
- **DWR's completed offline: Mobile Inspector**
  - No service = No Problem
- **Immediate shared information, Reports!**
  - DWR's from other inspectors are viewable to all, even in Draft form
- **Combined Databases**
  - QPL, EquipmentWatch, Certifications, and more to come

# GDPR to DWR Demo

**General Daily Progress Report** Print Form

**Project Information**

DWR Testing 02 ACM 12345  
 Project Name (Default) Contract No.  
 US30 Lower Columbia Highway S092(066)  
 Highway Federal Aid No.  
 Slegmund Excavation & Construction Inc Joe Smith Supervisor Present?  Yes  No  
 Contractor / Subcontractor On-Site Supervisor

**Weather** Reset

Clear	Fair	Cloudy	Shower	Rain	Snow
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TEMP	10-32	32-50	50-70	70-83	Over 83
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
WIND	Still	Low	Med	High	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
HUMIDITY	Dry	Low	Med	High	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

The first four columns are fixed and cannot be changed. In each of the remaining columns, please enter a heading specific to your job (e.g., Trainers, Backhoe, Flaggers) and record the numbers used by each contractor or sub.

Operations	Truck/Drivers	Laborers	TCS	F50	F250													
1																		
		2	1	1	1													

**Location and/or Description of Work** Estimated Quantities

Add Item		Item No.	This Date	Total
STA 1+00 to 8+00	Delimiters, Type 1	0420	10	30
STA 1+00 to 8+00	MP Marker Posts	0430	2	22
STA 1+00 to 8+00	TMA - Truck Mounted	0150	1	1
Various	TCS	0040	1	6

**Temporary Traffic Control** Photo(s)  Yes  No

All traffic control items have been inspected and found to be satisfactory  Yes  No (if no, explain below)

Contractor installed Cones on the shoulder of the roadway from STA 1+00 to 8+00 on US30. TMA is used to protect shoulder work in areas where no guardrail is installed. Shoulder width maintained for TPAR access.

**Equipment** Photo(s)  Yes  No

Impact Attenuator Truck, F150, F250

**Effects on Work (weather, accidents, breakdowns, delays, personnel, etc.)** Photo(s)  Yes  No

Traffic Control Issue, discussed TPAR bike lane access issue on shoulder. Baker Rock corrected issue and resumed work after 1 hour.

Anita Muhly 50661  
 Prepared by Cart No. Signature  
 Day  Sunday  Monday  Tuesday  Wednesday  Thursday  Friday  Saturday 17-Jan-23  
 Date Work Date

734-3474 (11-09-2018) 1



**Contract Daily Work Report Summary**

Contract: DWR Testing 02 ACM - Building data for DWR

DWR Date: 01/17/2023 Inspector: hwy41x Sequence: 1 Status: Draft

**General** DWR Date \* 01/17/2023 Remarks

**Notes** Inspector \* hwy41x Muhly Anita 4

**Contract Time** Federal Project Number S092(066)

**Contractors On Site** State Project Number

**Contractor Equipment** Weather Light Rain - Rain Less than 1/2 inch

**Contractor Personnel** Rainfall Amount 0.25

**Contractor Staff** Low Temperature 50

**Agency Staff** High Temperature 70

**Postings** Stormwater Event No

**Acceptance Records** Contractors Onsite Yes

**Force Account Contractors** Daily Staff Onsite Yes

**Remarks**

Type *	Remark *	Created Dt
Effects on Work - Accidents, Breakdowns, Delays, et...	Traffic Control issue; discussed TPAR bike lane access issue on shoulder. Baker Rock corrected issue and resumed work after 1 hour.	01/17/2023 10:32:02 PM
TC - Temporary Traffic Control	Contractor installed Cones on the shoulder of the roadway from STA 1+00 to 8+00 on US30. TMA is used to protect shoulder work in areas where no guardrail is installed. Shoulder width maintained for TPAR access.	01/17/2023 10:32:02 PM
Rejected Items - Materials, Equipment, etc...	None	01/17/2023 10:32:02 PM
DWRComment - DWR Comment	7:00 AM Inspector and Slegmund arrive on site. 8:00 AM Baker Rock Arrives on site.	01/17/2023 10:32:02 PM

**Agency Views**



# DWR Continued Resources

DWR Subcommittee is **dedicated to making the Inspector's work easier**

- DWR's and Diaries Subcommittee every other Thursday from 2:00 PM – 3:00 PM
- Contact Vanessa or Anita

## Mobile Inspector Demo

Topic: APOST Construction DWR & Diaries Subcommittee

Date: Mar 4, 2021 04:37 PM Eastern Time (US and Canada)

Copy the link below to share this recording with viewers:

<https://infotechinc.zoom.us/rec/share/Q78rgpH6Z622GhFz06RAKsKAuE-McNcTmmcy10wBHtO2AixwXI-72yLqYqnhZlw.kNYY63Y6vobMIpQo>

Passcode: M5!.t6^P

Register for an AASHTOWare Account: <https://www.aashtowareproject.org/home>

# Questions?

Anita Muhly, P.E.

Resident Engineer – Consultant Projects

AWP DWR & Diaries Subcommittee Team Lead

[Anita.MUHLY@odot.oregon.gov](mailto:Anita.MUHLY@odot.oregon.gov)

Cell: 971-403-8522

Best way to Contact: Teams Chat!

Contract Daily Work Report Summary

▼ Contract: DWR Testing 02 ACM - Building data for DWR

DWR Date: 01/17/2023 Inspector: hwye41x Sequence: 1

General	<b>DWR Date *</b> 01/17/2023
Notes	<b>Inspector *</b> hwye41x Muhly Anita
Contract Time	<b>Weather</b> Light Rain - Rain Less than 1/2 inch ▼
Contractors On Site	<b>Rainfall Amount</b> 0.25
Contractor Equipment	<b>Low Temperature</b> 50
Contractor Personnel	<b>High Temperature</b> 70
Contractor Staff	
Agency Staff	
Postings	
Acceptance Records	
Force Account Contractors	

